

#### PROJECT BACKGROUND







Rawalpindi Development Authority



Lahore Ring Road
Authority





Zeeruk International (Pvt.) Limited in Joint Venture with M/s Engineering General Consultants EGC (Pvt.) Limited







NESPAK in JV with KPMG and Axis Law

#### **PROJECT BENEFITS**

Ease congestion on urban transportation system of Rawalpindi and Islamabad.



Prompt Rawalpindi city's decongestion by identifying urban clusters along Ring Road.



Facilitate the growth of the Rawalpindi city towards southwestern side in a planned manner.



Curtail travel time and cost for road users.



#### PROJECT SALIENT FEATURES



65.3 Km



04 current 05 future






04 (02 both sides)




**3 + 3 lanes** 



60 M - 110 M




#### **DISTRICTS BOUNDARY ON RRR**



#### PROPOSED TYPICAL CROSS SECTION (PERSPECTIVE VIEW)




# TYPICAL CROSS SECTION START POINT TO HAKLA DI KHAN INTERCHANGE



# TYPICAL CROSS SECTION ALONG HAKLA – DI KHAN MOTORWAY (HAKLA INTERCHANGE TO M-1)

Existing R.O.W = 100 m



# TYPICAL CROSS SECTION M-1 TO SANGJANI INTERCHANGE

Proposed ROW = 60 m




#### PRELIMANRY DESIGN OF INTERCHANGE (RADIO PAKISTAN)




#### PRELIMANRY DESIGN OF INTERCHANGE (MURAT)



#### PRELIMANRY DESIGN OF INTERCHANGE (HAKLA DI KHAN)



#### PRELIMANRY DESIGN OF M1 CROSSING



#### PRELIMANRY DESIGN OF SANGJANI INTERCHANGE




#### TECHNICAL PARAMETRERS

Description	No of Structures (approx.)
Box Culverts	94
Cattle Creeps	17
Underpasses	7
Overpasses	10
Bridges Nullah / River	9
Soan River	Length = 560 m
Sil River	Length = 140 m
Interchange Bridges	17

Description	Detail
Type of Terrain	Plain / Rolling
Lane Width	3.6m x 3
Median Barrier	0.6 m (NJB Type
Max. Grade	3 %
Max. Super Elevation	6 %
Drainage	Both side
Electrification	Along project length
ITS	Full corridor

#### COMMITMENTS



**Private Investor** 

**Government** 



**Govt Approvals** 

Design

Build

**Finance** 

**Operate** 

Maintenance

Transfer to the Govt.

Govt. Support (VGF)





















#### Traffic Snapshot









Toll related to traffic travelling from/to Hakla DI Khan and M1 will be shared between RDA/concessionaire and NHA. — 50% traffic to be used for R3 Revenue

#### **Financials**

## Project Cost: PKR 35-40 Billion

Standard M-2 tariff **Tariff** 



Annual increase 7 %

**Toll Rates Escalation** 



25 Years (Including 2 years Construction period)

Concession period





Applicable Law

Punjab PPP Authority Act 2019



Project IRR: > 13%

Equity IRR: > 17%



Equity & Commercial Loan

Minimum equity: 30% Maximum debt: 70%



**VGF** 

VGF in the form of debt available. Payable after repayment of commercial debt

Windfall **Revenue Sharing** 





MRG (Open for discussion)

Revenue Sharing

# ALTERNATE OPTIONS TO MRG

### FUTURE INTERCHANGES





- Govt. to collect toll from future interchanges
  - Minimum Revenue Guarantee below 80% (50:50)



Concessionaire to collect toll from future interchanges

 No Minimum Revenue Guarantee (MRG)

**OPTION** 

Windfall gain sharing above 120% (70:30)



OPTION

Revenue sharing between Govt. and concessionaire for future interchanges Windfall gain sharing above 120% (60:40)

OPTION 1

#### **Government Support**

1

Upfront VGF during construction

2

Provincial support agreement

3

Restriction on unnecessary heavy traffic from entering into the city

4

Minimum Revenue Guarantee (MRG) below 80% during first 10 years - Optional

5

Revenue from future interchanges to be built by Govt.

/ 3<sup>rd</sup> party - Optional





# Government

 Right of way Risk (Incl. Land and shifting of utilities)



- Force Majeure Risk
- Demand Risk
- Regulatory Risk
- Environmental Risk

Subject to DCA Terms & Condition



**Private Part** 

#### Technical Specifications Risk Completion Risks Cost overrun Risk

- Design Risk
- Inflation Risk
- Insolvency Risk
- Insurance Risk
- Financing Risk
- Maintenance Risk
- Resource Risk
- Technology obsolescence Risk
- Utilities Risk O&M (Allied)
- Hand back Compliance risks Risk







Environmental Impact Assessment









PPP Project
Proposal submitted
in PPP Cell





Govt. released Rs. 6.2 B for land acquisition





Alignment Finalized









**Land Acquisition** 



#### RAWALPINDI RING ROAD PROJECT SCHEDULE

Q4 2O20

PPP Project Proposal Submitted Land Acquisition Process

Started

Environmental Approval Granted

Q2 2021

Bid Evaluation Contract Award Q4 2021

Financial Closure and Construction start

Q1 2021

PPP Project Proposal Approval
Public Notice for Bidding
Land Acquisition

Q3 2021

Financial Closure Process Q1 2022 - Q4 2023

**Construction Completion** 



#### **ECONOMIC CORRIDOR ALONG RRR**

